

Introduction

What is MiC?

Modular-Integrated Construction

What is DfMA?

Design for Manufacturing & Assembly

What is PPVC?

Prefabricated Prefinished Volumetric Col

What is MTP?

Multi-Trade Prefabrication

What is MiMEP?

MultiTrade Integrated Mechanical, Electrical & Plumbing

MEP components and equipment integrated into a sub-assembly off-site and then deliver to and installed on site.











Why MiMEP

- Shortage of skilled labour & aged construction workers
- Congested services within limited MEP space, plantrooms, headroom
- Uncoordinated services and installation sequencing
- Industrialized Construction, Construction
 4.0 & Digitalization
- Adoption & acceptance of BIM

Construction 4.0

An Innovation Platform for the Built Environment







Benefits


- Savings in construction time
- Less on site manpower as majority fabrication & assembly process completed off-site and reduces labour intensive site works
- Concurrent on-site & off-site construction and fabrication
- Higher consistency in quality by using precision & automatic machineries & quality assurance of MEP works in 360 degree access on the assemblies under controlled factory fabrication environment



- Minimize labour intensive works at height & enhance site safety
- Reduce noise, dust pollution, hot works & construction waste
- Reduce material wastage with neatly construction site
- Reduce abortive works with earlier identification of conflicts



Benefits





- Project driven to construction & assembly driven
- Modularity, high repetition with low variations
- Statutory compliance
- Building compartmentation & joints
- Room dimensions, columns, core walls, cross bracing
- Construction access and left-out












- Vertical and horizontal connections
- Alignment of MEP services compensation
- Large assemblies
- Transportation from factory to site and to place
- Structural rigidity for module handling, lifting points for hoisting, supporting frameworks dimensions & weights
- Site construction tolerance & installation allowance
- Structural connection between modules
 & with in-situ











BS services included	Electrical and ELV trunkings, AC ductwork and VAV boxes
Location	3F Training Workshop (40 x 10.5m)
Module Size	4.8m x 2.2m x 1.4m
No. of Modules	18
Types of Modules	3

























Delivery on-site by Lorry


Ready for Installation






- Size of each MiMEP 4.8m x 2.2m x 1.4m (LxWxH)
- Total 18 modules
- Reserving 1.2m
 jointing zone among
 modules
- Space to facilitate the lifting platform for installation
- Use of unistrut for minor lateral/vertical movement for alignment adjustment





















Success Factors

- Clients' know what they want
- Open minded, accept of new technologies & innovations
- Early design decisions & finalization
- BIM for coordination & collaboration with virtual design & construction
- Supply chain management, planning with just-in-time approach for module installation – factory assembly, delivery, hoisting, installation & final connections
- Allowance of flexibility for mis-alignment
- Use of snap-fits, couplings & adhesive bonding rather than bolts
 & nuts, screw joints, etc. for final connections
- Competent integrated multi-trade MEP contractors
- Mindset change, partnership & early involvement with MEP contractors





Thank you!

Acknowledgement of Photos:



ATAL BS Engineering Ltd.
China State M&E Engineering Ltd.
FSE Engineering Ltd.
Gammon E&M Ltd.
REC Engineering Ltd.



