

14 December 2022


MiC logistics and supply chain QA/QC during the COVID-19 pandemic time: A trilogic solution based on BIM and blockchain

Prof. Wilson Lu
Department of Real Estate and Construction
The University of Hong Kong,
Pokfulam, Hong Kong,





1. Starting from Construction 2.0




https://www.psgo.gov.hk/assets/pdf/Construction-2-0-en.pdf

With the assistance of KPMG published in Sep 2018




The Construction cost in HK is the third highest in the world

Cost



Average age of skilled construction workers is 52



Techniques

There is a decrease in construction techniques



2. MiC as a response to the Construction 2.0 report as a strategy of procurement innovation

Modular Integrated Construction (MiC) is an innovative construction method. By adopting the concept of "factory assembly followed by on-site installation", MiC helps to ease some of the current challenges faced by the local construction industry. In this method, free-standing integrated modules (completed with finishes, fixtures and fittings) are manufactured and assembled in a factory. By transferring on-site construction processes to a controlled factory environment, buildings can be substantially completed off-site. The adverse impacts of weather conditions, scarce labour resources and site constraints can all be substantially reduced. MiC provides a great degree of production quality control, and can improve construction productivity, safety and sustainability.

Source: CIC website

BIM integration

MiC facilitates the use of BIM within the design and construction phase.



Improved site safety

Some procedures can be carried out in a controlled factory environment.

Less waste and reduced carbon footprint

Factory construction facilitates a reducing in waste and carbon footprint also.





Shortened construction period

Due to controlled nature, tasks can be run parallel reducing the construction timeframe.

Improved supply chain

A reduction in external variables leads to improved supply chain management



Improved quality control

Factory automation leads to improved quality control.

Less local disruption

Disruptive construction activities can be relocated off-site





Less potential for contractual claim

A more controlled work environment leads to less potential for contractual claim.

Courtesy: HKU Estate Office





3. MiC logistics and supply chain QA/QC during the difficult time







3. MiC logistics and supply chain QA/QC during the difficult time



Quality inspections required at Mainland factories



Infeasible to dispatch now due to 14 + 14 days quarantines

(Photo source: Authors, SCMP)





4. Our trilogy (MiC 三寶)



Mobile Platform

Digitalization of MiC





4. Our trilogy (MiC 三寶)



Off-Site Production

- **Digitalized** workflow procedures
- Detailed record of inspection records carried out by AP/RSE/RC streams
- Test reports uploads
- Production progress status



Cross Boarder Logistics

- Real time tracking of modules during transportation
- Pin point exact location of module
- Estimated arrival time



On-Site Installation

- Real time update of installation progress
- Positioning checking for installed modules
 - Recording of installation time






4. Our trilogy (MiC 三寶)







4. Our trilogy (MiC 三寶)








4. Our trilogy (MiC 三寶)

Off-Site Production Workflow









THE UNIVERSITY OF HONG KONG 香港大學 faculty of architecture 建築學院



Department of Real Estate and Construction 房地產及建設系

4. Our trilogy (MiC 三寶)

Inspection Record



Two Factor Authentication



User ID





Scan Module ID







Inspection status of module









4. Our trilogy (MiC 三寶)

Inspection Record







Comment box

Help button

Photo upload function







4. Our trilogy (MiC 三寶)

Blockchain visualization












4. Our trilogy (MiC 三寶)

Dashboard









e-InStar








4. Our trilogy (MiC 三寶)

It is used on a daily basis throughout the 40+ steps, all 900 modules!










4. Our trilogy (MiC 三寶)




Logistics: *i*-core and blockchain oracle

The i-Core sensors and smart address systems are one of the development tools with multi-functions to monitor both the logistics and installation of MiC modules



i-Core sensors and smart address plates are installed in the MiC modules





4. Our trilogy (MiC 三寶)

Logistics: *i*-core and blockchain oracle



i-core Generation I

i-Core sensors are installed in the MiC modules





i-core Generation II






i-core Generation III





4. Our trilogy (MiC 三寶)

Logistics: *i*-core and blockchain oracle










4. Our trilogy (MiC 三寶)



Logistics: app









4. Our trilogy (MiC 三寶)

e-TranStar Logistics on your finger tips

Dashboard













5. Acknowledgement and prospects


Web-base dashboard



App











THE UNIVERSITY OF HONG KONG 香港大學 faculty of architecture 建築學院

Department of Real Estate and Construction 房地產及建設系

5. Acknowledgement and prospects







A MiC digital transformation trilogic solution (MiC三寶)

Organisation
The University of Hong Kong (HKU)

Funding Scheme
Government Innovation and Technology Fund

2.5 Years (1-Jan-2021 to 30-Jun-2023)

Introduction (e.g. project summary and

objectives)

Modular integrated Construction (MiC) is a game-changing innovation to address the many challenges related to Hong Kong's construction industry, e.g., declining productivity, escalating cost, unsatisfactory safety record, and aging labor force. However, its power cannot be fully harnessed without the processes being digitally transformed. This research project aim to develop a trilogy of MiC digital transformation solution by focusing on its offsite fabrication ('factory'), cross-border logistics ('road'), and onsite assembly ('site'). The final product is formed by three apps organized on a BIM-blockchain enabled platform:

- e-InStar: For remote e-inspection of MiC quality in factory;
- · e-TranStar: For e-monitoring MiC logistics on road; and
- . e-InstallStar: For e-planning and monitoring MiC installation. All the information will be simultaneously displayed in web BIM, kept in a database, and safeguarded in a blockchain system.

Research activities in the project (e.g. research methodology, work progress and next stage of

The research project adopts BIM, i-Core (An award-winning IoT technology), and blockchain technologies. An iteration of 'lab development' and 'field test' has been conducted over the past two years to achieve the objectives. The research progresses well by successfully developing the e-InStar and e-TranStar and we are now working on the e-InstallStar. The product has been implemented in HKU's hostel MiC projects. Next stage, we will scale up the solution to other MiC projects.

Collaboration with industry/government sectors, if applicable

Funding support:

Logistics and Supply Chain MultiTech R&D Centre (LSCM)

The Innovation and Technology Fund (ITF) Government support:

The Development Bureau The Construction Industry Council

Industrial support: Estate Office, The University of Hong Kong

Research products/patents produced, if applicable

The trilogic solution is almost finished their development. The e-Instar and e-TranStar are used in daily operation.

Principal Investigator
Professor Wilson LU, Prof. Anthony Yeh, Ir. Mr. KL Tam, Dr Frank Xue

HK\$10.36m (including industrial sponsor)

Project Status

Achievements of project objectives

- Construction Industry Council (CIC) "Celebration of BIM
- Achievement 2022" Award (Category: BIM Projects) · ASCE (American Society of Civil Engineering), Best Paper
- Award of Journal of Management in Engineering 2022

 buildingSMART International Awards 2021 (Category:
- Professional Research)
- Construction Industry Council (CIC) Construction Digitalisation Award 2021 (Silver, Category: Training/Research Institute)

Research findings

A combination of BIM, blockchain, i-Core, and other technologies has been innovatively integrated together to form a good solution for MiC produced in factory, cross-border transportation, and on-site installation. It can:

- · Ensure the visibility and traceability of MiC throughout its production circle;
- Guarantee offsite production quality during the COVID-19 pandemic era:
- Ensure the immutability of the records: and
- · Ensure the quality and productivity of MiC.

Impact/application to the community

The project was well connected from the outset with the stakeholders, including the government, the CIC, client, industrial partners, and other suppliers.

The solution is used in HKU WCH MiC project on a daily basis in inspecting the quality of its 900+ modules. It is also used for MiC cross-border transportation monitor. The research is finalizing the installation app.

Great impacts have been achieved by engaging with the frontliner practitioners, government bodies, funding agencies, interested stakeholders and the general public.

Some "taste" sessions using robotics and MiC installation have been organized with hundreds of secondary school

The project is being scaled up to other types of MiC





5. Acknowledgement and prospects



港大遙距電子檢測系統 奪智慧物流金獎

2022-11-18 00:00



港大研發電子檢測系統,跨境遙距監察組裝合成建築模塊的質量,獲香港資訊 及通訊科技智慧物流金獎。





5. Acknowledgement and prospects



iLab members Dr Jinying Xu and Mike Wu received the ASCE Journal of Management in Engineering (JME) Best Paper Award 2022 on in California, USA



港大研區塊鏈技術應用於組裝合成工程 獲選土木工程界最佳論文

香港大學建築學院iLab團隊研究人員關於應用區塊鏈技術於 hk.on.cc

港大研區塊鏈技術應用於組裝合成工程 獲選土木工程界最佳論文

https://hk.on.cc/hk/bkn/cnt/news/20221110/bkn-20221110010024365-1110_00822_001.html





5. Acknowledgement and prospects



HKU Wong Chuk Hang (WCH) project won the Celebration of BIM Achievement (CBA) in 2022 – 'BIM Project' Category






5. Acknowledgement and prospects



OpenBIM and Blockchain integration (OBBi)





港大研建築信息模型新技術 贏國際大獎賽

2021-10-21 03:23



港大研建築信息模型新技術,贏得國際大獎賽。(前排左起)徐進英博士,呂 偉生教授和薛帆博士;(後排左起)吳劉鵬飛和趙銳。受訪者提供。





5. Acknowledgement and prospects

e-instar 2.0: From single project to portfolio; from small to big flats





From Wong Chuk Hang to High West





5. Acknowledgement and prospects


Tesla factories for MiC QA/QC, Accreditation



a) A snapshot of a prefabrication factory in the Pearl River Delta (PRD) region of China (Source: authors, 2010)



of China (Source: authors, 2020)









5. Acknowledgement and prospects

Digital transforming MiC

Digital transformation of modular integrated construction (MiC): Synergizing management theories, construction practices, and digital technologies





Thank you!

